

縦断測量成果整理表（１）

平成 18 年度測量

距離標杭諸元					縦断成果				計画諸量						
距離標 No.	流心区 間距離 m	流心区 間追加 距離 m	左岸距離 標追加距 離 m	右岸距離 標追加距 離 m	距離標高		堤防高		計画 河床高 m	計画高 水敷高 m	計画高 水位高 m	計画 築堤高 m	計画 河床 勾配	計画 高水 勾配	計画 粗度
					左 岸 m	右 岸 m	左 岸 m	右 岸 m							
115.0K	0	0	0	0	310.111	316.196					309.11				
115.2K	190	190	193	192	310.758	311.052					309.11				
115.4K	189	379	321	435	312.406	311.822					309.68				
115.6K	209	588	430	732	312.438	310.199					310.46				
115.8K	209	797	599	940	310.644	311.937					310.57				
116.0K	193	990	728	1195	311.800	309.845					310.74				
116.2K	192	1182	891	1414	310.494	312.470					311.34				
116.4K	196	1378	1058	1639	311.945	314.844					311.88				
116.6K	196	1574	1263	1820	310.646	310.691					311.81				
羽衣崎橋	171	1745	1444	1985	320.896	322.662					311.88				
116.8K	74	1819	1523	2057	315.764	311.521					312.05				
117.0K	134	1953	1738	2087	312.676	311.387					312.97				
117.2K	224	2177	2002	2219	312.081	312.491					313.07				
117.4K	208	2385	2212	2418	312.590	312.135					313.64				
117.6K	200	2585	2411	2622	310.069	315.147					313.90				
117.8K	200	2785	2552	2875	310.953	310.881					314.09				
118.0K	194	2979	2693	3117	311.688	310.545					314.00				
118.2K	194	3173	2879	3317	309.847	313.399					314.69				
118.4K	209	3382	3133	3451	313.677	311.034					315.38				
118.6K	208	3590	3326	3637	312.483	313.983					316.03				
118.8K	197	3787	3523	3839	313.391	313.333					316.33				
119.0K	196	3983	3696	4052	313.865	310.438					316.53				

縦断測量成果整理表（１）

平成 18 年度測量

距離標杭諸元					縦断成果				計画諸量						
距離標 No.	流心区 間距離 m	流心区 間追加 距離 m	左岸距離 標追加距 離 m	右岸距離 標追加距 離 m	距離標高		堤防高		計画 河床高 m	計画高 水敷高 m	計画高 水位高 m	計画 築堤高 m	計画 河床 勾配	計画 高水 勾配	計画 粗度
					左 岸 m	右 岸 m	左 岸 m	右 岸 m							
119.2K	200	4183	3734	4364	313.460	311.752					316.83				
119.4K	200	4383	3888	4467	311.572	314.462					316.61				
119.6K	198	4581	4134	4529	313.052	310.432					317.01				
119.8K	197	4778	4307	4721	310.967	310.487					317.34				
120.0K	197	4975	4528	4886	312.935	310.666					317.52				
天竜橋	5	4980	4534	4889	320.321	320.300					317.50				
120.2K	193	5173	4766	5013	310.525	313.547					318.72				
120.4K	165	5338	4985	5115	311.820	309.786					318.73				
120.6K	252	5590	5244	5262	313.495	313.470					318.88				
120.8K	202	5792	5378	5539	311.483	312.487					318.69				
121.0K	202	5994	5557	5745	313.730	314.791					319.16				
121.2K	190	6184	5728	5945	314.063	311.407					319.31				
121.4K	190	6374	5910	6128	313.528	311.526					319.48				
121.6K	207	6581	6098	6350	313.432	311.135					319.61				
121.8K	206	6787	6275	6571	313.642	314.483					320.30				
122.0K	207	6994	6507	6721	313.521	314.865					320.59				
122.2K	206	7200	6728	6873	314.371	312.299					320.61				
122.4K	195	7395	6959	7098	311.035	312.385					320.91				
122.6K	194	7589	7003	7354	314.082	314.005					321.20				
122.8K	198	7787	7111	7614	316.123	312.078					321.26				
123.0K	197	7984	7328	7821	316.564	312.885					321.32				
123.2K	199	8183	7524	8028	314.144	314.461					321.45				

縦断測量成果整理表（１）

平成 18 年度測量

距離標杭諸元					縦断成果				計画諸量						
距離標 No.	流心区 間距離 m	流心区 間追加 距離 m	左岸距離 標追加距 離 m	右岸距離 標追加距 離 m	距離標高		堤防高		計画 河床高 m	計画高 水敷高 m	計画高 水位高 m	計画 築堤高 m	計画 河床 勾配	計画 高水 勾配	計画 粗度
					左 岸 m	右 岸 m	左 岸 m	右 岸 m							
123.4K	198	8381	7725	8211	314.399	313.454					321.40				
123.6K	193	8574	7946	8378	319.641	313.768					321.56				
南宮大橋	81	8655	8010	8486	328.968	338.744					321.71				
123.8K	111	8766	8098	8634	317.368	316.011					321.92				
124.0K	202	8968	8248	8919	317.349	312.465					321.95				
124.2K	202	9170	8453	9109	320.823	314.086					321.94				
124.4K	200	9370	8665	9297	314.785	316.105					321.96				
124.6K	200	9570	8876	9474	313.574	316.401					322.16				
124.8K	202	9772	9094	9664	310.516	316.864					322.07				
125.0K	201	9973	9307	9807	313.849	313.827					322.25				
125.2K	202	10175	9527	9986	313.970	315.932					322.67				
竜田橋	171	10346	9698	10153	331.839	331.775					322.64				
125.4K	31	10377	9730	10184	317.404	313.125					322.76				
125.6K	200	10577	9932	10385	315.462	317.000					324.03				
125.8K	199	10776	10120	10589	313.730	317.112					324.20				
126.0K	208	10984	10343	10778	312.908	312.345					324.78				
126.2K	207	11191	10541	10990	317.231	315.200					325.41				
126.4K	200	11391	10688	11224	319.029	319.135					325.45				
126.6K	199	11590	10891	11412	316.459	319.697					325.92				
126.8K	195	11785	11079	11615	317.883	319.355					325.84				
127.0K	195	11980	11267	11814	318.171	324.522					325.91				
127.2K	211	12191	11482	12017	314.454	319.765					325.87				

平成 18 年度測量

[illegible]